

David A. Tyler, Architect
101 South Center Street
Thomaston, Georgia 30286
706-647-4692 dt Tyler177@charter.net
Member A.I.A.

ADDENDUM NO.3

DATE: Monday July 13, 2010

TO: Prime Contractors

RE: A New Medical Office Building
Barnesville, Georgia

The following items shall take precedence over the plans and specifications for the above named project. This addendum is now made a part of the contract documents. All other requirements of the original documents remain in effect.

GENERAL.

Elevator as supplied by Genesis Elevators will not be accepted.

General note for soundboard and gyp board in Addendum #2 should read " 12" above finish ceiling"

SPECIFICATIONS.

ITEM 1: Section 01500 -Temporary Facilities and Controls- Delete Article 1.3.B and C.

ITEM 2: Section 15170- Plumbing Piping, Valves and Specialties- PVC is acceptable.

ITEM 3: Section 15805- Roof Curbs, Equipment Rails and Accessories.

This section covers equipment rails for roof mounted condensing units.

DRAWINGS

ITEM 1: Sheets A6.1, A6.3, and A6.3 Wall Sections- Add typical note “ 5/8" TYPE “X” GYP BD” at bottom chord of trusses.

ITEM 2: Sheet A7.1 Architectural Room Finish

Delete Carpet @ lease Space 284.

ITEM 3: Sheet E2.1 First Floor Power Plan

Panel L3 shall be located at Hall 187 on column line #6

ITEM 4: Sheet E7.1 Panel Schedule- Replace sheet E7.1 with revised sheet attached.
This sheet includes the schedule for panel L7.

End of Addendum #3